

PROVINCIAL GOVERNMENT OF DAVAO DE ORO

Cabidianan, Nabunturan, Davao de Oro

TECHNICAL SPECIFICATIONS FORM

Bid Number: B-25-0142 Purchase Request Number: 24-4709 04/30/2025 Date:

1 of 1 Page:

| | | | T | | | <u> </u> | |
|-------------|------|------------------|--|-----------------|--------------|------------|--------------|
| ITEM NO. | QTY. | UNIT OF ISSUE | DESCRIPTION | APPROVED BUDGET | | BID PRICES | |
| | | | | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | 1.0 | lot | Supply & Installation of Glass Windows for the Rehabilitation of Dairy Milking Parlor, Storage & Selling area | 105,577.50 | 105,577.50 | | |
| | | | Window 1: 5 units 1.2m x 1.2m Window, 2 panel Sliding Window with 5.5mm-6.0mm thk. Brown Glass on std. Analok Rectangular Tube 45mm x 100mm with Expanded Wire and Screen Mesh, locks, handles and rollers | | | | |
| | | | Window 2: 2 units 0.60m x 1.80m, 3 panel Awning Window with 5.5mm-6.0mm thk. Bronze Glass in Snap-on Analok Aluminum U- clip Moulding with cam handle & forebar hinges | | | | |
| | | | Window 3: 1 unit 0.60m x 1.20m, 2 panel Awning Window with 5.5mm-6.0mm thk. Bronze Glass in Snap-on Analok Aluminum U- clip Moulding with cam handle & forebar hinges | | | | |
| | | | Window 4: 1 unit 0.60m x 0.60m, 1 panel Awning Window with 5.5mm-6.0mm thk. Bronze Glass in Snap-on Analok Aluminum U- clip Moulding with cam handle & forebar hinges | | | | |
| | | | Window 5:1 unit 1.2m x 0.65m Window, 1 panel Casement Window with 5.5mm-6.0mm thk. Bronze Glass on std. hanalok rectangular tube 45mm x 100mm with locking and opening mechanism | | | | |
| | | | Window 6: 3 units 1.2m x 1.8m Fixed Window, 5.5mm-6.0mm thk. Fixed Bronze Glass on std. Analok Rectangular tube 45mm x 100mm | | | | |
| | | | Window 7: 1 unit 1.2m x 1.8m Window, 3 panel Sliding Window with 5.5mm-6.0mm thk. Bronze Glass on std. Analok Rectangular Tube 45mm x 100mm with Expanded Wire and Screen Mesh, locks, handles and rollers | | | | |
| | | | | | | | |
| | | | | TOTAL/LOT | 105,577.50 | | |

Purpose: For Rehabilitation of Agricultural Infrastructure

Delivery: DDO Farm, Pasian, Monkayo

Period of Delivery: 20 days